This electronic collection of documents is provided for the convenience of the user and is Not a Certified Document –

The documents contained herein were originally issued and sealed by the individuals whose names and license numbers appear on each page, on the dates appearing with their signature on that page.

This file or an individual page shall not be considered a certified document.

UTILITY CONSTRUCTION

UC-27 UTILITY NOTES:

1.PURSUANT TO TRAFFIC CONTROL REQUIRMENTS, CONTRACTOR MUST BE COMPLETE WITH WORK ON THE SOUTH SIDE OF RAEFORD ROAD BEFORE BEGINNING WORK ON THE NORTH SIDE. CONTRACTOR SHALL NOT BE PERFORMING WATER MAIN INSTALLATION LONGITUDINALLY TO THE ROAD ON BOTH SIDES.

2.WL-25 IS TO PROVIDE SOURCE WATER TO FACILITATE INSTALLATION SEQUENCE FOR WL-26 BETWEEN 12" IN-LINE VALVE AT STA. 40+15 TO 12" IN-LINE VALVE AT STA. 30+64.

3.WL-26 BETWEEN IN-LINE VALVE AT APPROX. STA. 30+64 TO THE IN-LINE VALVE AT APPROX. STA. 40+15 SHALL BE INSTALLED AND FULLY OPERATIONAL, INCLUDING FORSYTHE DRIVE CROSS-LINE CONNECTION, PRIOR TO CONNECTION TO PREVIOUSLY INSTALLED WL-25 SEGMENT. (SEE UTILITY NOTES FOR SHEET UC-32)

4.PROPOSED WL-26 BRANCH VALVE (APPROX. STA. 40+34) SHALL BE INSTALLED AND REMAIN CLOSED. THE INSTALLATION OF THE PORTION OF WL-26 CROSSING RAEFORD ROAD SHALL BE OPEN CUT SIMULTANIOUSLY WITH THE PROPOSED 24"PARALLEL DRAINAGE PIPE.

5.ALL EXISTING METERS THAT OVERLAP THIS RELOCATION SEGMENT SHALL BE SWITCHED OVER TO THIS NEW SEGMENT. CROSS LINE IN FORSYTHE ROAD SHALL BE FULLY RESTRAINED THROUGH BRANCH VALVES.

6.THE NEXT IN-LINE VALVE FOR EXISTING 6"WATER LINE LOCATED IN FORSYTHE DRIVE IS APPROX. 400 LF FROM TIE-IN CONNECTION AND HAS A LOOPED SYSTEM AND AN EXISTING VALVE AT THE INTERSECTION OF BREEZEWOOD AVE APPROX. 370 LF FROM TIE-IN LOCATION. CONTRACTOR TO COORDINATE WITH THE ENGINEER TO FACILITATE TEMPORARY SHUTDOWN.

7.CONTRACTOR SHALL CONNECT TO EXISTING 6"WATER MAIN USING FULLBODY SLEEVE AND RESTRAINING GLANDS. THIS PART OF THE CONNECTION SHALL BE SWABBED PRIOR TO RECONNECTION OF THE EXISTING 6" WATER MAIN. THE EXISTING CROSS LINE AT FORESYTHE DRIVE SHALL BE KILLED OUT BY PERMANENTLY CLOSING AND ABANDONING EXISTING VALVE EV-102. KILL OUT SHALL BE DONE BETWEEN 9:00 P.M. TO 6:00 A.M. TO COMPLY WITH TRAFFIC CONTROL REQUIREMENTS.

8.WL-26 FROM 12"BRANCH VALVE (APPROX. STA. 40+34) TO 12"IN-LINE VALVE (APPROX. STA. 41+10) AND 12"X12"X12"TEE (APPROX. STA. 42+25 WL-28) SHALL BE INSTALLED, RESTRAINED, AND FULLY OPERATIONAL PRIOR TO MOVING TO INSTALLATION OF WL-28.

9.WL-28 BETWEEN THE 12"X8"REDUCER (APPROX. STA. 41+95) TO 12"X12"X12"TEE (APPROX. STA. 45+22) SHALL BE INSTALLED AND FULLY OPERATIONAL PRIOR TO MOVING TO INSTALLATION OF WL-27. THIS INSTALLATION SHALL BE PERFORMED BETWEEN 9:00 P.M. AND 6:00 A.M. ALL OPEN EXCAVATIONS SHALL BE PLATED AND READY FOR TRAFFIC BY 6:00 A.M. UNLESS EXCAVATIONS ARE BACKFILLED/COMPACTED AND PATCHED BY 6:00 A.M.

10.WL-27 BETWEEN 12"IN-LINE VALVE (APPROX. STA. 0+13) TO 6"X6"X6"TAPPING SLEEVE AND VALVE ON AMIGO DRIVE (APPROX. STA. 8+67), INCLUDING WL-30 FROM 6"x6"x6"TAPPING SLEEVE & VALVE ON SOUTH SIDE OF RAEFORD ROAD SHALL BE INSTALLED AND OPERATIONAL PRIOR TO TIE-IN OF EXISTING 12"WATER MAIN IN MCPHEE DRIVE.

11.ALL EXISTING METERS THAT OVERLAP THIS RELOCATION SEGMENT SHALL BE SWITCHED OVER TO THIS NEW SEGMENT. CROSS LINE IN FORSYTHE ROAD SHALL BE FULLY RESTRAINED THROUGH BRANCH VALVES.

12.THE EXISTING 12"WATER MAIN LOCATED IN MCPHEE DRIVE HAS AN IN-LINE VALVE APPROX. 83 FEET FROM TIE-IN LOCATION. SINCE EXISTING 12-INCH WATER MAIN MAY NOT BE RESTRAINED, THERE IS A LOOPED SYSTEM AND FOUR EXISTING VALVES IN MCBAIN DRIVE (EV-118, EV-119, EV-120 AND EV-121) TO FACILITATE SHUTDOWN FOR KILL-OUT OF EXISTING 12"CI WATER MAIN. CONTRACTOR TO COORDINATE WITH THE ENGINEER TO FACILITATE TEMPORARY SHUTDOWN.

13.CONTRACTOR SHALL CONNECT TO EXISTING 12" WATER MAIN USING FULLBODY SLEEVE AND RESTRAINING GLANDS. THIS PART OF THE CONNECTION SHALL BE SWABBED PRIOR TO RECONNECTION OF THE EXISTING 12"WATER MAIN. THE EXISTING 12"WATER MAIN AT MCPHEE DRIVE SHALL BE KILLED OUT BY PERMANENTLY CLOSING AND ABANDONING EXISTING VALVE EV-107. KILL OUT SHALL BE DONE BETWEEN 9:00 P.M. TO 6:00 A.M. TO COMPLY WITH TRAFFIC CONTROL REQUIREMENTS AND MINIMIZE SERVICE INTERUPTION.

14.EXISTING VALVES, EV-112, EV-113, EV-109, EV-111, EV-110 AND IN-LINE VALVE NEAR CLUB CIRCLE (APPROX. 578 FEET FROM EV-113) TO FACILITATE SHUTDOWN FOR KILL-OUT OF EXISTING 6"CI WATER MAIN. PLANNED SHUT DOWN SHALL BE COORDINATED WITH THE ENGINEER.

15.KILL OUT OF EXISTING WATER MAIN AT THE INTERSECTION OF AMIGO DRIVE AND RAEFORD ROAD SHALL INCLUDE THE ABANDONMENT OF 60 LF OF 6"PIPE AND SHALL BE PER PWC DETAIL W.22

16.WL-29 SHALL BE BUILT OUT FROM TAPPING SLEEVE & VALVE. NEXT IN-LINE VALVE TO FACILITATE SHUTDOWN OF WL-29 IS APPROXIMATELY 187 LF FROM PROPOSED RECONNECTION POINT.

17.CONNECT EXISTING 2"WATER MAIN TO NEW 8"WATER MAIN USING SADDLE TAP.

UC-27 UTILITY NOTES

18.CONTRACTOR SHALL CONNECT TO EXISTING 6"WATER MAIN USING FULLBODY SLEEVE AND RESTRAINING GLANDS. THIS PART OF THE CONNECTION SHALL BE SWABBED PRIOR TO RECONNECTION OF THE EXISTING 6" WATER MAIN. THE EXISTING 6"WATER MAIN AT FAIRWAY DRIVE SHALL BE KILLED OUT BY PERMANENTLY CLOSING AND ABANDONING EXISTING VALVE EV-111. KILL OUT SHALL BE DONE BETWEEN 9:00 P.M. TO 6:00 A.M. TO COMPLY WITH TRAFFIC CONTROL REQUIREMENTS AND MINIMIZE SERVICE INTERUPTION.

19.WL-28 BETWEEN THE 12"X8"REDUCER (APPROX. STA. 41+95) TO THE NEXT 8"IN-LINE VALVE (APPROX. STA. 37+58 ON SHEET UC-26) SHALL BE INSTALLED AND FULLY OPERATIONAL PRIOR TO INSTALLING WL-28 SECTION BETWEEN IN-LINE VALVES (APPROX. STA. 27+22 AND APPROX. STA. 37+58) ON SHEET UC-26. THE INSTALLATION BETWEEN HORIZONTAL 45 DEGREE BEND (APPROX. STA. 40+45) AND THE 12"X8"REDUCER (APPROX. STA. 41+95) SHALL BE PERFORMED BETWEEN 9:00 P.M. AND 6:00 A.M. ALL OPEN EXCAVATIONS SHALL BE PLATED AND READY FOR TRAFFIC BY 6:00 A.M. UNLESS EXCAVATIONS ARE BACKFILLED/COMPACTED AND PATCHED BY 6:00 A.M.

20.ALL EXISTING METERS THAT OVERLAP THIS RELOCATION SEGMENT SHALL BE SWITCHED OVER TO THIS NEW SEGMENT.

UC-27A UTILITY NOTES:

1.TEMPORARY SHORING IF REQUIRED FOR BUILDING FOUNDATION PROTECTION OR MAINTENANCE OF TRAFFIC WILL BE PAID AS TEMPORARY SHORING IN SQUARE FEET BELOW GROUND SURFACE.

2.CONTRACTOR SHALL SUBMIT A DETAILED SEWAGE BYPASS PLAN FOR MAINTAINING ALL SEWAGE FLOWS THAT WILL BE IMPACTED BY THE SEWER RELOCATION AND ADHERE TO ALL REQUIREMENTS IN OWNER'S WASTE WATER CONTROL SPECIFICATIONS.

3.CONTRACTOR SHALL VERIFY SEWER SERVICE DEPTH AND LOCATION PRIOR TO ORDERING MATERIALS.

4.CONTRACTOR SHALL REPLACE EXISTING CLEAN OUT AND SEWER SEVICE LINE AT SAME DEPTH AND SLOPE.

5.CONTRACTOR SHALL REMOVE EXISTING CLEAN OUT AND EXISTING SEWER SERVICE TO PROPOSED CLEAN OUT LOCATION. CONTRACTOR SHALL GROUT FILL EXISTING SERVICE CORE IN MANHOLE WITH NON-SHRINK GROUT.

6.CONTRACTOR SHALL COORDINATE WITH DRAINAGE INSTALLATION OF 15"AND 18" STORM PIPE BETWEEN DRAINAGE STRUCTURE 2734, 2724 AND 2725 TO REPLACE 200 FEET OF EXISTING 12"VCP PIPE WITH DIP AT SAME SLOPE.

UC-32 UTILITY NOTES:

1.PURSUANT TO TRAFFIC CONTROL REQUIRMENTS, CONTRACTOR MUST BE COMPLETE WITH WORK ON THE SOUTH SIDE OF RAEFORD ROAD BEFORE BEGINNING WORK ON THE NORTH SIDE. CONTRACTOR SHALL NOT BE PERFORMING WATER MAIN INSTALLATION LONGITUDINALLY TO THE ROAD ON BOTH SIDES.

2.WL-25 FROM 12"x12"x12" TAPPING SLEEVE & VALVE ON ROBESON STREET, INCLUDING CROSS-LINE CONNECTION CWL-EY46 TO IN-LINE VALVE APPROX. STA. 40+15 ON WL-26 AND 12"BRANCH VALVE APPROX. STA. 40+34 ON WL-26 (SEE UTILITY NOTES ON UC-27) SHALL BE INSTALLED AND OPERATIONAL.

3.ALL EXISTING METERS THAT OVERLAP THIS RELOCATION SEGMENT SHALL BE SWITCHED OVER TO THIS NEW SEGMENT. CROSS-LINE IN CWL-EY46 SHALL BE FULLY RESTRAINED THROUGH BRANCH VALVES.

4.EXISTING IN-LINE VALVE, EV-106 (AT INTERSECTION OF RAEFORD RD AND ROBESON ST, AND EXISTING 12" IN-LINE VALVE LOCATED APPROX. 685 LF FROM APPROX. TIE-IN LOCATION TO FACILITATE SHUTDOWN FOR KILL-OUT OF EXISTING 12" AC WATER MAIN. PLANNED SHUT DOWN SHALL BE COORDINATED WITH THE ENGINEER.

5.KILL OUT OF EXISTING 12 "AC WATER MAIN AT PROP. 12" TAPPING SLEEVE AND VALVE SHALL INCLUDE FULLY GROUT OF 60 LF OF 12"PIPE AND SHALL BE PER PWC DETAIL W.22

6.CWL-EY46 AN 8"CUT-IN VALVE SHALL BE INSTALLED BETWEEN 9:00 P.M. AND 6:00 A.M. TO MINIMIZE SERVICE INTERUPTION. EXISTING IN-LINE VALVE EV-115 (IN FAIRWAY DRIVE), EV-114 (IN ROBESON ST), AND EXISTING BRANCH VALVES EV-116 AND EV117 TO FACILITATE SHUTDOWN FOR INSTALLATION OF 8"CUT-IN VALVE. PLANNED SHUT DOWN SHALL BE COORDINATED WITH THE ENGINEER.

7.AFTER INSTALLATION OF 8"CUT-IN VALVE, CONTRACTOR SHALL CONNECT TO EXISTING 8"WATER MAIN USING FULLBODY SLEEVE AND RESTRAINING GLANDS OUTSIDE OF EXISTING 16"ENCASEMENT. THIS PART OF THE CONNECTION SHALL BE SWABBED PRIOR TO RECONNECTION OF THE EXISTING 8"WATER MAIN. THE CROSS-LINE SHALL BE KILLED OUT BY PERMANENTLY CLOSING AND ABANDONING EXISTING VALVE EV-106. IF THERE IS NOT ENOUGH EXISTING 8"WATER MAIN PIPE BETWEEN EXISTING ENCASEMENT AND EXISTING 12"X 8" TAPPING SLEEVE AND VALVE (EV-114) TO CONNECT TO, CONTRACTOR SHALL PROPERLY REMOVE EXISTING 12"X 8"TAPPING SLEEVE (EV-114) AFTER KILL OUT OF EXISTING 12"WATER MAIN.

PROJECT REFERENCE	NO.	SHEET NO.
U-4405		UC-3G
DESIGNED BY: AMH		8/8/2018
DRAWN BY: AMH/AB		CAROLINA CESSION
CHECKED BY: AMH		OFESS 101 NA
APPROVED BY: MWF		SEAL 025490
REVISED:		025490 E
NORTH CAROLINA DEPARTMENT OF TRANSPORTATION		ARK W. FISHERILLE
UTILITIES ENGINEERING SEC. PHONE: (919)707-6690 FAX: (919)250-4151	UTI	Mork W. Lister LIBESDF64F25S4DRUCTION PLANS ONLY

UC-33 UTILITY NOTES:

UTILITY CONSTRUCTION

1.CONTRACTOR SHALL SUBMIT A DETAILED SEWAGE BYPASS PLAN FOR MAINTAINING ALL SEWAGE FLOWS THAT WILL BE IMPACTED BY THE SEWER RELOCATION AND ADHERE TO ALL REQUIREMENTS IN OWNER'S WASTE WATER CONTROL SPECIFICATIONS.

2.CONTRACTOR SHALL VERIFY SEWER SERVICE DEPTH AND LOCATION PRIOR TO ORDERING MATERIALS.


3.SL-8 SHALL BE INSTALLED AND OPERATIONAL FROM EXIST MANHOLE AT STA. 0+00 TO PROP. MANHOLE MH-4 AT STA. 7+35.71 PRIOR TO INSTALLING 4"SEWER SERVICE IN PROP. MANHOLE MH-4, SL-9 AND SL-10.


4.CONTRACTOR SHALL RETAIN DOWNSTREAM PORTION OF EXISTING SEWER OF PROP. MH-4 SO EXISTING 4" SEWER SERVICE CAN REMAIN ACTIVE UNTIL NEW SEWER IS READY FOR SERVICE LATERAL RELOCATION.

5.INSTALLATION OF SL-9 AND SL-10 SHALL BE COORDINATED WITH INSTALLATION OF SL-8. MAINTAIN FLOW CONTROL PROVISIONS WHEN CONSTRUCTING SL-9 AND SL-10. BYPASS PUMP AND PIPIING TO MAINTAIN SEWER FLOW DURING CUT IN CONSTRUCTION SHALL BE SITUATED TO MAINTAIN TRAFFIC FLOW.

6.AFTER SEWER IS INSTALLED AND OPERATIONAL WITHIN EXECUTIVE PLACE, CONTRACTOR SHALL PLUG INVERT OF 12" INSIDE EXISTING MANHOLE LOCATED IN RAEFORD ROAD. THIS WORK SHALL BE PERFORMED BETWEEN 9:00 P.M. AND 6:00 A.M. TO MINIMIZE TRAFFIC IMPACTS.

Shoring	Begin Station & Offset		Estimated Average Height	Estimated Maximum Height	Shoring Location Type	Square	Trench
ocation No.	_	67+66.02 -L-, 37.17'	(ft)	(ft)	Roadway (Longtitudinal	Footage (ft)	Length (
No. 1	Right	Right	6.5	10.81	Trench)	715	50
No. 2	76+01.08 -L-, 182.28' Left	76+10.56 -L-, 181.02' Left	9.55	9.71	Roadway Shoulder (Perpendicular Trench)	286.5	10
No. 3	98.92.49 -L-, 221.06' Left	99+11.68 -L-, 226.64' Left	6.75	6.75	Bore (Receiving) Within Roadway	270	10
	134+33.75 -L-, 41.97'	134+33.75 -L-, 52.97'			Bore (Receiving)		
No. 4	Left 135+62.47 -L-, 74.20'	Left 135+62.49 -L-, 84.20'	4.25	4.55	Adjacent to Roadway Bore (Receiving)	170	10
No. 5	Right 153+80.37 -L-, 38.39'	Right 154+94.88 -L-, 46.14'	10	10	Adjacent to Roadway Roadway (Longitudinal	400	10
No. 6	Right	Right	6	6	Trench)	1500	120
No. 7	184+34.82 -L-, 77.40' Right	185+44.40 -L-, 57.10' Right	7	12	Roadway (Longitudinal Trench)	1820	125
No. 8	187+94.38 -L-, 59.94' Right	188+60.72 -L-, 90.74' Right	5	5	Roadway (Longitudinal Trench)	1300	125
No. 9	190+60.99 -L-, 61.16' Right	190+61.05 -L-, 71.16'	6.25	6.5	Bore (Receiving)	250	10
NO. 9	190+60.30 -L-, 65.72	Right 190+59.92 -L-, 95.72			Adjacent to Roadway Bore (Jacking) Adjacent		
No. 10	Right 220+74.37 -L-, 41.38	Right 220+47.04 -L-, 62.55	5.3	5.3	to Roadway Roadway Shoulder	636	40
No. 11	Left	Left	8	8	(Perpindicular Trench)	640	20
No. 12	209+39.92 -L-, 71.75 Left	209.+59.92 -L-, 71.65 Left	6.5	6.5	Roadway Shoulder (Longitudinal Trench)	325	20
No. 13	215.30.54 -L-, 64.76 Left	223+33.67 -L-, 51.76 Left	8	13	Roadway Shoulder (Longitudinal Trench)	13280	825
	253+62.17 -L-, 41.37	255+57.16 -L-, 53.56			Roadway (Longitudinal		
No. 14	Left 258+57.39 -L-, 67.23	Left 259+47.75 -L-, 41.43	9	9.5	Trench) Roadway (Longitudinal	3690	200
No. 15	Left 257+96.91 -L-, 46.56	Left 261+40.32 -L-, 40.75	6.5	6.5	Trench) Roadway (Longitudinal	1365	100
No. 16	Right	Right	8	8	Trench)	5744	354
No. 17	260+63.52 -L-, 18.16 Left	260+63.85 -L-, 28.16 Left	14	14	Roadway (Perpindicular Trench)	280	5
	261+00.09 -L-, 19.80	261+01.34 -L-, 59.78			Bore (Jacking) Within		
No. 18	Left 270+59.58 -L-, 76.12	Left 270+66.67 -L-, 75.60	10	14	Roadway Roadway Shoulder	1200	40
No. 19	T .	Right	5.5	5.5	(Longitudinal Trench)	1705	150
No. 20		279+30.51 -L-, 19.79 Right	10	10	Roadway (Perpindicular Trench)	200	5
		282+25.82 -L-, 19.63			Roadway (Perpindicular		_
No. 21	_	Right 284+69.72 -L-, 19.56	10	10	Trench) Roadway (Perpindicular	200	5
No. 22	Right	Right	8.9	8.9	Trench)	178	5
No. 23	285+35.91 -L-, 24.55 Right	285+35.91 -L-, 19.55 Right	8.9	8.9	Roadway (Perpindicular Trench)	178	5
110. 20	287+70.59 -L-, 24.69	287+70.59 -L-, 19.69	0.0	0.0	Roadway (Perpindicular	110	
No. 24	Right	Right	10	10	Trench)	200	5
No. 25	288+40.99 -L-, 24.65 Right	288+40.99 -L-, 19.65 Right	10	10	Roadway (Perpindicular Trench)	200	5
	288+89.31 -L-, 24.65	288+89.31 -L-, 19.65			Roadway (Perpindicular		
No. 26	Right 289+22.62 -L-, 24.66	Right 289+22.62 -L-, 19.66	10	10	Trench) Roadway (Perpindicular	200	5
No. 27	Right	Right	10	10	Trench)	200	5
No. 28	289+75.62 -L-, 24.68 Right	289+75.62 -L-, 19.68 Right	13	13	Roadway (Perpindicular Trench)	260	5
	289+91.63 -L-, 27.39	289+91.63 -L-, 27.39			Roadway (Perpindicular		
No. 29	Right 291+47.33 -L-, 16.03	Right 291+47.33 -L-, 11.03	13	13	Trench) Roadway (Perpindicular	260	5
No. 30	Right 292+18.90 -L-, 15.41	Right 292+18.90 -L-, 10.41	12	12	Trench) Roadway (Perpindicular	240	5
No. 31	Right	Right	12	12	Trench) Roadway (Perpindicular	240	5
No. 32	Right	292+64.20 -L-, 11.06 Right	12	12	Trench)	240	5
No. 33	293+74.37 -L-, 16.08 Right	293+74.37 -L-, 11.08 Right	12	12	Roadway (Perpindicular Trench)	240	5
	295+01.74 -L-, 16.08	295+01.74 -L-, 11.08			Roadway (Perpindicular		
No. 34	Right 296+86.13 -L-, 15.76	Right 296+86.13 -L-, 10.76	11	11	Trench) Roadway (Perpindicular	220	5
No. 35	Right	Right	11	11	Trench)	220	5
No. 36	300+02.08 -L-, 15.62 Right	300+02.08 -L-, 10.62 Right	11	11	Roadway (Perpindicular Trench)	220	5
	300+73.89 -L-, 15.66	300+73.89 -L-, 10.66			Roadway (Perpindicular		
No. 37	Right 303+69.68 -L-, 15.32	Right 303+69.68 -L-, 10.32	11	11	Trench) Roadway (Perpindicular	220	5
No. 38		Right	11	11	Trench)	220	5
No. 20	304+82.28 -L-, 15.72	304+82.28 -L-, 10.72	44	4.4	Roadway (Perpindicular	220	_
No. 39	Right 308+20.09 -L-, 15.47	Right 308+20.09 -L-, 15.47	11	11	Trench) Roadway (Perpindicular	220	5
No. 40	· ·	Right 308+27.12 -L-, 10.46	12	12	Trench) Roadway (Perpindicular	240	5
No. 41	Right	Right	13	13	Trench)	260	5
No. 42	264+91.28 -L-, 299.05 Left	265+28.19 -L-, 314.24 Left	11	11	Bore (Entry) Within Roadway	1320	40
	265+83.32 -L-, 337.57	266+01.74 -L-, 345.43			Bore (Receiving) Within		
No.43	Left	Left	11	11	Roadway	1100	40





MAIN/LATERAL, UNLESS LOCAL CONDITIONS OR BARRIERS PREVENT A

ii. THE WATER MAIN IS LAID IN THE SAME TRENCH AS THE SEWER

A WATER MAIN TO CROSS OVER A SEWER MAIN/LATERAL, THE WATER MAIN SHALL BE LAID AT SUCH AN ELEVATION THAT THE BOTTOM OF THE WATER

LINEESS LOCAL CONDITIONS OR BARRIERS PREVENT AN 18 INCH VERTICAL

SEPARATION - IN WHICH CASE BOTH THE WATER MAIN AND SEWER

MAIN AND THE SEWER MAIN/LATERAL SHALL BE DUCTILE IRON IN

THREE AND A HALF (3.5) FEET OF COVER MUST BE MAINTAINED OVER TH

WATER MAIN OR IT SHALL BE DUCTILE IRON. IF DUCTILE IRON PIPE IS USED

WATER MAIN AND A MINIMUM OF 4-INCHES OF VERTICAL CLEARANCE SHALL

7/01/16 ADDED NOTE 6

W1-WATER-UTILITY-NOTES.dwg

. ALL MATERIALS TO BE APPROVED BY

WATER SERVICE LOCK VALVE TO BE

LOCATED 18" FROM SANITARY SEWER

CLEANOUT STACK WHEN INSTALLED IN

WHEN INSTALLED IN A PAVED AREA,

METER BOX TO BE SET 1/4" ABOVE

FINISHED PAVEMENT GRADES AND

PROVIDE DRAIN AWAY FROM BOX.

WHERE ASPHALT CURB OR STRIP

8. DISTANCE FROM TOP OF LOCK VALVE

BE 8" MINIMUM TO 10" MAXIMUM.

9 RESIDENTIAL METER BOX SHALL BE SET

BOX PERPENDICULAR TO THE R/W.

BUILDING TO EDGE OF BOX).

UNLESS OTHERWISE NOTED.

14. BARB-TYPE FITTINGS ARE NOT

07/06 RESIZED METER COUPLING

BOTTOM VIEW

—— 12**-**5/16" ——

ELEVATION (A)

NO. DATE

REVISION

03/10 CHANGED BOX DIMENSIONS

05/29/18 REVISED NOTES 1 FOR NCDOT U-4405

W4-1IN-METERBOX.dwg

07/13 REVISED NOTE RE: TRACER WIRE 07/17 REVISED NOTES

INCLUDE PLACEMENT OF BOX 18"

WITHIN PUE ON SECTION AND PLAN

W2-WLAT.dwg

05/29/18 REVISED NOTES 1, 7, AND 12 AND

ACCEPTABLE

11 LATERAL SHALL BE CENTERED ON LOT

COMMERCIAL METER BOX LOCATION

SHALL BE AS APPROVED (PREFER NO. METER BE INSTALLED LESS THAN 5' FROM

COMPOSITE METER BOXES SHALL BE

USED IN TRAFFIC AREAS SEE FAYPWC

INSTALL NCDOT CONCRETE BRICK BASE

WITH NO GAPS. DO NOT LAY BRICK ON

SHALL BE AS DIRECTED BY ENGINEER.

PAVEMENT EXISTS, THE LOCATION OF BOX

OPERATING STEM TO TOP OF BOX SHALL

18" FROM R/W TO CENTERLINE OF METER

LATERAL SHALL NOT BE BACKFILLED UNTIL

INSPECTED AND APPROVED BY ENGINEER.

HYDROSTATIC AND STERILIZATION TESTS.

WATER SERVICE LATERAL, A FULL CIRCLE

REPAIR CLAMP SHALL BE PLACED ON THE

13. WATER MAIN AND LATERAL SHALL PASS

PAVEMENT FEATHERED TO TOP OF BOX TO

SERVICE LATERAL SIZE 1" IPS POLYETHYLENE UNLESS OTHERWISE

SPECIFIED.

SAME DITCH.

DETAIL W.4B.

PIPE. SEE INSET "A".

2 OF 2

DATE: JAN. 01, 2018 APPROVED BY: J.E.G.

WHERE A WATER MAIN CROSSES UNDER A STORM DRAINAGE LINE THE

MINIMUM OF TWELVE (12) INCHES OF VERTICAL SEPARATION SHALL BE

OF 10-FEET ON EACH SIDE OF THE CROSSING.

-12" METER COUPLING

THREAD METER SWIVEL

SPACER SHALL

BE CENTERED

IN METER BOX

WITH 3/4" FEMALE

NUT x 3/4" MIPT

-1"x7-1/2" SPACER FOR

DOMESTIC SERVICE,

1"x10-3/4" SPACER FOR

FURNISHED BY FAYPWC

IRRIGATION SERVICE,

NCDOT CONCRETE BRICK

METER BOX BASE SEE

<u>PLAN</u>


SPACER SHALL BE

MAIN/LATERAL WITH THE WATER MAIN LOCATED AT ONE SIDE ON A

BENCH OF UNDISTURBED EARTH AND WITH THE ELEVATION OF THE

10-FOOT LATERAL SEPARATION - IN WHICH CASE:

THE SEWER MAIN/LATERAL.



ENGINEERING DEPARTMENT

FOR NCDOT U-4405


W1-WATER-UTILITY-NOTES.dwg





UTILITY CONSTRUCTION


NOTE_


ANY REFERENCE TO FAYPWC PROJECT COORDINATOR, PWC COORDINATOR OR FAYPWC (FAYETTEVILLE PUBLIC WORKS COMMISSION) SHALL BE INTERPRETTED AS A REFERENCE TO THE ENGINEER.











ENGINEERING DEPARTMENT

PRECAST REINFORCED CONCRETE.

VALVE BOX SHALL BE AT GRADE WITH

PROTECTOR RING EXTENDING 1/2" ABOVE

VALVE BOX PROTECTOR RINGS SHALL BE

HINDRANCE TO MOWING OPERATIONS.

CUT AWAY VIEW

REVISION

NO. DATE

INSTALLED AROUND VALVE BOX IN UNPAVED

DEFORMED BAR AS SHOWN

FAYETTEVILLE

FAYETTEVILLE, N.C.

WATER RESOURCES

ENGINEERING DEPARTMENT

PUBLIC WORKS COMMISSION

RING IS EXPOSED,

REMAINDER IS BURIED.

DATE: JAN. 01, 2018 APPROVED BY: J.E.G.

PLAN N.T.S.

VALVE BOX $^{\perp}$


24" DIAMETER MINIMUM


SECTION A-A N.T.S.

VALVE BOX PROTECTOR RING

DWG. NO. W.8 DWG. BY: FAYPWC


DATE: JAN. 01, 2018 APPROVED BY: J.E.G.







NOTE:


ANY REFERENCE TO FAYPWC PROJECT COORDINATOR, PWC COORDINATOR OR FAYPWC (FAYETTEVILLE PUBLIC WORKS COMMISSION) SHALL BE INTERPRETTED AS A REFERENCE TO THE ENGINEER.









W10-M.J.-TAPPING-SLEEVE.dwg










UTILITY CONSTRUCTION

NOTE:


ANY REFERENCE TO FAYPWC PROJECT COORDINATOR, PWC COORDINATOR OR FAYPWC (FAYETTEVILLE PUBLIC WORKS COMMISSION) SHALL BE INTERPRETTED AS A REFERENCE TO THE ENGINEER.










W15A-2-VALVE-INSTALLATION.dwg









PROJECT REFERENCE NO. SHEET NO. U−4405 UC-03L 8/3/2018 DESIGNED BY: AMH DRAWN BY: AMH/AB CHECKED BY: AMH APPROVED BY: MWF 025490 REVISED: NORTH CAROLINA DEPARTMENT OF TRANSPORTATION Mark W. fish JTILITIES ENGINEERING SEC PHONE:(919)707-6690 FAX:(919)250-4151

UTILITY CONSTRUCTION

NOTE:

SECTION "B-B'

SECTION "A-A"

90° 45° ELBOW 22-1/2°

OR DEAD END.

RESTRAIN M.J. JOINTS WITH IRON

M.I. RESTRAINT RETAINING

ELBOWS & CROSSES ELBOWS

ANY REFERENCE TO FAYPWC PROJECT COORDINATOR, PWC COORDINATOR OR FAYPWC (FAYETTEVILLE PUBLIC WORKS COMMISSION) SHALL BE INTERPRETTED AS A REFERENCE TO THE ENGINEER.

TRANSITION TO D.I. PIPE (TYP.)

UNRESTRAINED AT JOINT

RESTRAIN M.J. JOINTS

M.J. GATE VALVE WITH

APPROVED RESTRAINT

WITH APPROVED

RESTRAINT (TYP.)

–MJ. TEE WITH

POINT OF D.I. PIPE TRANSITION TO

C900 OR D.I. PIPE (TYP.)

- ALL D.L. PIPE BETWEEN FITTING AND

VALVE SHALL BE RESTRAINED ALL

DIRECTIONS.

- M.J. GATE VALVE WITH

APPROVED RESTRAINT

DUCTILE IRON PIPE (TYP.)

DI PIPE TRANSITION TO

UNRESTRAINED AT JOINT

C900 OR D.I. PIPE

- C900 OR D.I. PIPE

-RESTRAIN M.I. JOINTS WITH

APPROVED RESTRAINT (TYP.)

5 THE MINIMUM LENGTH OF

ENGINEER PRIOR TO

RESTRAINT SYSTEMS MAY

VARY BASED UPON THE

ENGINEERS' DESIGN AS

SHOWN ON THE PLAN AN

GRIPPER RING AND FIELD LOK

SIZES WHERE FACTORY

METHOD OF RESTRAINT ON

RESTRAINT JOINTS MUST BE

DUCTILE IRON PIPE ONLY. SEE

SPECIAL PROVISIONS FOR MAIN

RESTRAINT INDICATED SHALL

REQUIRE ALL JOINTS WITHIN

RESTRAINT SYSTEM SHALL BE

THE LR DISTANCE TO BE

(TYP.)

LR TEE

— R/W----

RESTRAINED JOINT DETAIL FOR TYPICAL TEE INTERSECTION

4-WAY INTERSECTION SIMILARLY RESTRAINED

I. THRUST RESTRAINT SHALL BE

INSTALLED ON DUCTILE IRON

WATER DISTRIBUTION LINES 6"

MANNER SHOWN. SEE FAYPWO

RESTRAINT OR OTHER FORMS

OF IRON RESTRAINT SHALL

NOT BE USED ON PVC PIPE

DIAMETER SHALL REQUIRE

ACCEPTABLE FOR USE WITH IRON RETAINING GLAND M.J.

THE PROPER LENGTH.

OF D.I. RESTRAINT.


RESTRAINED JOINT PIPE FOR

DETAIL W.17 FOR PVC

IRON RETAINING GLAND M.J.


LR VALVE LR VALVE

(TYP.)



DEPARTMENT

DATE: JAN. 01, 2018 APPROVED BY: J.E.G.



2. SUITABLE BEDDING MATERIAL SHALL EXTEND TO

3. IF GROUND CONDITIONS WARRANT, IT MAY BE NECESSARY TO

1 01/01/17 REVISED NOTES

07/01/13 REVISED NOTE RE: TRACER WIRE

05/29/18 REVISED NOTES FOR NCDOT U-4405

W19-WATER-BEDDING.dwg

BED DUCTILE IRON WATER MAINS IN SELECT BEDDING MATERIAL (NO. 5 OR NO. 57 STONE) TO THE SPRINGLINE OF THE PIPE. SUCH INSTALLATION SHALL BE AS DIRECTED BY

UNDISTURBED TRENCH WALLS.

MANHOLE BASE SECTION

4"x8"x16" SOLID CONCRETE

BLOCKS STACKED 2 HIGH 180°

SHALL BE SUPPORTED ON

FAYETTEVILLE

PUBLIC WORKS COMMISSION

WATER RESOURCES

ENGINEERING DEPARTMENT

<u></u>UNDISTURBED

- 4" MIN. SUITABLE SOIL BEDDING

FROM TRENCH EXCAVATION

- SUBBASE SHALL BE UNDISTURBED

INSUITABLE BY THE ENGINEER

UNDERCUT AND BACKFILLED WITH

SELECT BEDDING MATERIAL (SEE

SOIL. WHERE SOIL IS DEEMED

AUTHORIZED AREA SHALL BE

FAYETTEVILLE

PUBLIC WORKS COMMISSION

FAYETTEVILLE, N.C.

WATER RESOURCES

(SEE NOTE 1)

FAYETTEVILLE, N.C.

NO. 5 STONE DRAINAGE PIT

COMBINATION AIR RELEASE

CONTINUOUS 12 GA. -

COPPER WIRE OR

TO VALVE BOX)

WATER MAIN BEDDING DETAIL

DWG NO. W 19 DWG BY: FAYPWC

DATE: JAN. 01, 2018 APPROVED BY: J.E.G. ENGINEERING DEPARTMENT

SINGLE STRAND COATED

COPPER CLAD STEEL

RACING WIRE REQUIRED


FOR ALL NON-FERROUS


PIPE (FROM VALVE BOX

VACUUM VALVE (WATER SERVICE)

DWG NO. W 16 DWG BY: FAYPWC

DATE: JAN. 01, 2018 | APPROVED BY: J.E.G.






W20-METER-VAULT.dwg


SIDE VIEW

FRONT VIEW

RESTRAINT

IRON RETAINING GLAND M.J. RESTRAIN





BALL VALVE

COUPLING -

2" LATERAL, INSTALLED IN —

2" BRASS F.I.P x PACK-

INLET/OUTLET

JOINT FOR PVC ADAPTOR

CONTINUOUS NCDOT -

DWG NO. W.28 DWG BY: FAYPWC

2 OF 2 DATE: JAN. 01, 2018 APPROVED BY: J.E.G.

BASE FOR METER BOX.

CONCRETE BRICK SUPPORT

ACCORDANCE WITH

DETAIL W.30.

WIRE

2" IRRIGATION LATERAL

N.T.S.

CONTINUOUS NCDOT

CONCRETE BRICK ∠METER SETTER ASSEMBLY SEE SHEET 2 OF 2.

12" BRASS NIPPLE -

FAYETTEVILLE

PUBLIC WORKS COMMISSION

WATER RESOURCES

ENGINEERING DEPARTMENT

FAYETTEVILLE, N.C.

USE BENDS OF DIFFERENT

ANGLES AS NEEDED

BASE FOR METER BOX.

BY OTHERS

NO. DATE

REVISION

W28-2IN-IRRIG-LAT.DWG

07/17 REVISED NOTES, ADDED SHEET 2

05/29/18 REVISED NOTES 1, 3, 6 AND 7 FOR

NCDOT U-4405 07/24/18 REVISED PER NCDOT COMMENTS

2" BRASS FIP & PACK -

2" PVC SDR21 PIPE

DWG. NO. W.28 DWG. BY: FAYPWC

DATE: JAN. 01, 2018 | APPROVED BY: JEG

└─2"DIA BRASS BALL VALVE


2" IRRIGATION LATERAL

N.T.S.

∠2" TAPPING SADDLE

*SEE DETAIL W.15B FOR A

DETAIL OF THE 2" TAP*



PROJECT REFERENCE NO.

AMH/AB

UTILITY CONSTRUCTION

U-4405

DESIGNED BY: AMH

CHECKED BY: AMH

APPROVED BY: MWF

NORTH CAROLINA

DEPARTMENT OF TRANSPORTATION

JTILITIES ENGINEERING SEC

PHONE:(919)707-6690

FAX:(919)250-4151

DRAWN BY:

REVISED:

DI PIPE, LENGTH

AS REQUIRED

INSTALL MIN. ONE

FULL JOINT OF DI

AT CONFLICT

MJ DI 45° BENDS.

REVISION

W26-PIPE-RELOCATION-DETAIL.dwg

RELOCATION

IRON MJ RESTRAIN

RETAINING GLANDS


SHEET NO.


UC-O3M


SEAL


025490

Mark W. fish









FAYETTEVILLE

PUBLIC WORKS COMMISSION

FAYETTEVILLE, N.C.

WATER RESOURCES

NO. DATE

02/11/04 SIZING CHART

REVISION

ADDED 6" CARRIER PIPE TO BORE

07/10 REVISED NOTES, SIZING CHART

SECTION "A-A" CARBON STEEL CARRIER PIPE BRACE

BORE UNDER ROADWAYS/RAILROADS


DWG. NO. M.6 DWG. BY: FAYPWC

PROJECT REFERENCE NO. SHEET NO. U-4405 UC-03N DESIGNED BY: AMH DRAWN BY: AMH/AB CHECKED BY: AMH SEAL APPROVED BY: MWF 025490 REVISED: NORTH CAROLINA DEPARTMENT OF TRANSPORTATION JTILITIES ENGINEERING SEC PHONE:(919)707-6690 FAX: (919)250-4151

UTILITY CONSTRUCTION

NOTE:

ANY REFERENCE TO FAYPWC PROJECT COORDINATOR, PWC COORDINATOR OR FAYPWC (FAYETTEVILLE PUBLIC WORKS COMMISSION) SHALL BE INTERPRETTED AS A REFERENCE TO THE ENGINEER.



UTILITY GENERAL NOTES 1. PRIOR TO COMMENCEMENT OF ANY WORK WITHIN EASEMENTS OR 6. CONTRACTOR SHALL PROVIDE TEMPORARY SUPPORTS FOR RIGHTS-OF-WAYS THE CONTRACTOR IS REQUIRED TO NOTIFY UTILITY CROSSINGS AND REPAIR DAMAGES DUE TO CONSTRUCTION TO THE SATISFACTION OF THE UTILITY INVOLVED CONCERNED UTILITY COMPANIES IN ACCORDANCE WITH GS 87-102. AT NO ADDITIONAL EXPENSE TO THE OWNER. UNDERGROUND CONTRACTOR SHALL VERIFY LOCATION OF EXISTING UTILITIES PRIOR TO BEGINNING CONSTRUCTION. NO SEPARATE PAYMENT ELECTRICAL CROSSINGS SHALL BE CROSSED IN ACCORDANCE EXISTING UTILITIES SHOWN ARE TAKEN FROM MAPS FURNISHED WITH THE N.E.C. AND TECHNICAL SPECIFICATION SECTION BY VARIOUS UTILITY COMPANIES AND HAVE NOT BEEN PHYSICALLY UNDERGROUND ELECTRICAL CROSSING REQUIREMENTS. LOCATED (IE: TELEPHONE, GAS, CABLE, ETC.). WHERE DEEMED NECESSARY BY THE ENGINEER THAT A 2. THE CONTRACTOR SHALL DIG UP EACH UTILITY WHICH MAY SUBSURFACE DRAINAGE SYSTEM IS REQUIRED, THE CONTRACTOR CONFLICT WITH CONSTRUCTION 14 DAYS IN ADVANCE TO VERIFY SHALL PROVIDE ALL MATERIALS, TOOLS, LABOR, EQUIPMENT, LOCATIONS (HORIZONTALLY AND VERTICALLY) TO ALLOW THE TIE-IN'S TO EXISTING DRAINAGE STRUCTURES AND ALL OTHER IGINEER AN OPPORTUNITY TO ADJUST THE DESIGN TO AVOID IN ACCORDANCE WITH CITY OF FAYETTEVILLE STANDARDS. CONFLICTS (NO SEPARATE PAYMENT). IMPROPERLY INSTALLED AND NON-FUNCTIONING DRAINAGE SHALL 3. ALL SANITARY SEWER AND WATER CONSTRUCTION SHALL BE IN BE REMOVED AND REPLACED AT THE CONTRACTOR'S EXPENSE. ACCORDANCE WITH UTILITY SPECIAL PROVISIONS EXISTING FRENCH DRAINAGE DAMAGED DURING CONSTRUCTION STORM DRAINAGE. SHALL BE REPLACED AND/OR REPAIRED AT NO ADDITIONAL STREET CONSTRUCTION ADD PAVING SHALL BE IN ACCORDANCE EXPENSE TO THE OWNER. WITH THE CITY OF FAYETTEVILLE. STORM DRAINAGE REPAIRS BY CONTRACTOR DUE TO 4. UTILITY SERVICES TO INDIVIDUAL PROPERTIES ARE NOT SHOWN IN CONSTRUCTION DAMAGE AND JOINTS EXPOSED DURIN THE PROFILES FOR SIMPLICITY OF THE DRAWINGS. SERVICES MAY CONSTRUCTION SHALL BE INSPECTED BY THE OWNER PRIOR TO INCLUDE WATER LATERALS, TELEPHONE, ELECTRIC, CABLE, GAS, BACKFILLING. 5. CONTRACTOR SHALL COORDINATE WITH UTILITY OWNER AND BE RESPONSIBLE FOR TEMPORARY RELOCATION AND/OR SECURING EXISTING UTILITY POLES AND SIGNS AND/OR UTILITIES IN ACCORDANCE WITH UTILITY OWNER REQUIREMENTS DURING THE UTILITY MAIN INSTALLATION AND STREET CONSTRUCTION. (NO SEPARATE PAYMENT). FAYETTEVILLE NO. DATE **UTILITY GENERAL NOTES** PUBLIC WORKS COMMISSION 07/24/18 REVISED PER NCDOT COMMENTS FAYETTEVILLE, N.C. DWG. NO. N.2 DWG. BY: FAYPWC WATER RESOURCES ENGINEERING DEPARTMENT DATE: JAN. 01. 2018 | APPROVED BY: J.E.G.

HALF SECTION ISOMETRIC OF BORE

FAYETTEVILLE PUBLIC WORKS COMMISSION

FAYETTEVILLE, N.C.

WATER RESOURCES

ENGINEERING DEPARTMENT

BORE UNDER ROADWAYS/RAILROADS

DWG. NO. M.6 DWG. BY: FAYPWC

DATE: JAN. 01, 2018 APPROVED BY: J.E.G.

FACTORY RESTRAINED JOINTS.

FIELD LOC, SURE STOP 350 OR

OTHER APPROVED GASKETS

SHALL BE CLASS 50 FOR SEWER.

REVISION

10/09 CLARIFIED RESTRAINT REQUIREMENTS

M6-BORE-ROAD-RAIL.dwg

N2-UTILITY-NOTES.dwg

01/05 ADDED NOTES 2 AND 3

3. CARRIER PIPE SHALL BE CLASS 350 OR 250 FOR WATER, AND

SEWER SHALL HAVE RESTRAINED

CARRIER PIPE FOR GRAVITY

JOINTS AND MAY USE

NO. DATE

CONTRACTOR SHALL REPAIR ALL SEWER LATERALS AND MAINS DAMAGED DURING CONSTRUCTION. THE CONTRACTOR SHALL IMMEDIATELY REPORT ALL SEWER MAIN AND LATERAL BREAKS TO THE ENGINEER. THE CONTRACTOR SHALL INITIATE IMMEDIATE REPAIRS IN ACCORDANCE WITH THE UTILITY SPECIAL PROVISIONS

SEWER MAINS, LATERALS, AND MANHOLES SHALL BE INSTALLED UTILIZING AN APPROVED CUT-SHEET, INDICATING INSTALLATION DEPTH

TRANSFER OF SEWER SERVICES SHALL BE ACCOMPLISHED AS FOLLOWS: A. INSTALL AND TEST NEW MAINS, MANHOLES, AND LATERALS. CLEANOUTS SHALL BE INSTALLED 18" INSIDE R/W OR PUE UNLESS OTHERWISE DIRECTED BY

B. CONNECT EXISTING PLUMBING TO NEW LATERAL UTILIZING THE NECESSARY FITTINGS AS DIRECTED BY ENGINEER. C. AFTER ALL SERVICES HAVE BEEN TRANSFERRED TO THE NEW MAIN, THE EXISTING SEWER SYSTEM SHALL BE ABANDONED IN ACCORDANCE WITH THE UTILITY SPECIAL PROVISIONS.

WHEN THE EXISTING MAIN IS NOT TO BE ABANDONED, THE CONTRACTOR SHALL UNCOVER THE EXISTING LATERAL AT THE MAIN, CUT AND PLUG BOTH ENDS, REMOVE THE EXISTING CLEANOUT AND COMBINATION, AND PLUG THE LATERAL TO ABANDON

CONTRACTOR SHALL ABANDON ("KILL-OUT") ANY EXISTING SEWER SERVICES THAT WILL NOT BE LITHIZED BY LINCOVERING THE EXISTING LATERAL AT THE MAIN, CLIT AND PLUG AT BOTH ENDS, REMOVE THE EXISTING CLEANOUT AND COMBINATION, AND PLUG THE TAP OR TEE AT THE MAIN. FOR LATERALS THAT CONNECT TO A MANHOLE AND ARE TO BE ABANDONED ("KILLED-OUT"), THE LATERAL SHALL BE REMOVED FROM THE MANHOLE AND THE REMAINING VOID IN THE MANHOLE SHALL

BE FILLED WITH BLOCK AND MORTAR.

SHEET NO.

1 OF 1

SEWER PLUGS SHALL BE INSTALLED TO ELIMINATE ANY DEBRIS OR OTHER MATERIAL FROM ENTERING THE ACTIVE SEWER SYSTEM. UPON ACCEPTANCE OF THE NEW SEWER SYSTEM, THE CONTRACTOR SHALL CLEAN THE NEW MAINS, REMOVE ALL DEBRIS, AND THEN REMOVE THE PLUG

ALL EXISTING UTILITIES IMPACTED BY CONSTRUCTION SHALL BE ADJUSTED TO FINISHED GRADE, IN ACCORDANCE WITH ELEVATIONS INDICATED OR SHOWN ON

ALL WORK ON SEWER UTILITIES (MAINS, LATERALS, ETC) SHALL BE PERFORMED BY A LICENSED UTILITY CONTRACTOR. THE ENGINEER SHALL OBSERVE AND APPROVE ALL WORK ON SEWER UTILITIES. ALL WORK SHALL BE COMPLETED IN ACCORDANCE WITH THE UTILITY SPECIAL PROVISIONS.

> SEPARATION REQUIREMENTS A. LATERAL SEPARATION OF SEWERS AND WATER MAINS: WATER MAINS PROPOSED SEWER MAIN/LATERAL, UNLESS LOCAL CONDITIONS OR

BARRIERS PREVENT A 10-FOOT LATERAL SEPARATION - IN WHICH CASE i. THE WATER MAIN IS LAID IN A SEPARATE TRENCH, WITH THE ELEVATION $% \left(1\right) =\left(1\right) \left(1\right)$

ii. THE WATER MAIN IS LAID IN THE SAME TRENCH AS THE SEWER MAIN/LATERAL WITH THE WATER MAIN LOCATED AT ONE SIDE ON A BENCH OF UNDISTURBED EARTH AND WITH THE ELEVATION OF THE SOTTOM OF THE WATER MAIN AT LEAST 18 INCHES ABOVE THE TOP OF

OF THE BOTTOM OF THE WATER MAIN AT LEAST 18 INCHES ABOVE THE

B. CROSSING A WATER MAIN OVER A SEWER: WHENEVER IT IS NECESSARY FOR SHALL BE LAID AT SLICH AN ELEVATION THAT THE BOTTOM OF THE WATER MAIN IS AT LEAST 18 INCHES ABOVE THE TOP OF THE SEWER MAIN/LATERAL, UNLESS LOCAL CONDITIONS OR BARRIERS PREVENT AN 18 INCH VERTICAL SEPARATION - IN WHICH CASE BOTH THE WATER MAIN AND SEWER MAIN/LATERAL SHALL BE CONSTRUCTED OF FERROUS MATERIAL AND WITH JOINTS THAT ARE EQUIVALENT TO WATER MAIN STANDARDS FOR A DISTANCE OF 10 FEET ON EACH SIDE OF THE POINT OF CROSSING.

THE SEWER MAIN/LATERAL

C. CROSSING WATER MAIN UNDER A SEWER: WHENEVER IT IS NECESSARY FOR A WATER MAIN TO CROSS UNDER A SEWER MAIN/LATERAL, BOTH THE WATER MAIN AND THE SEWER MAIN/LATERAL SHALL BE CONSTRUCTED OF DUCTILE IRON MATERIAL AND WITH JOINTS EQUIVALENT TO WATER MAIN STANDARDS FOR A DISTANCE OF 10 FEET ON EACH SIDE OF THE POINT OF CROSSING. A SECTION OF WATER MAIN PIPE SHALL BE CENTERED AT THE POINT OF

D. CROSSING STORM DRAINAGE LINES: A MINIMUM OF 24-INCHES OF VERTICAL LEARANCE SHALL BE MAINTAINED BETWEEN A SEWER MAIN/LATERAL CROSSING UNDER A STORM DRAINAGE LINE UNLESS DUCTILE IRON PIPE IS USED. IF DUCTILE IRON PIPE IS USED, A MINIMUM OF SIX(6) INCHES OF SEPARATION SHALL BE MAINTAINED, UNLESS OTHERWISE APPROVED BY THE ENGINEER.

GENERAL NOTES				FAYETTEVILLE PUBLIC WORKS COMMISSION	PWC	NO.	DATE	REVISION
ANITARY SEWER UTILITY		TILITY	FAYETTEVILLE, N.C.	1		07/16	ADDED NOTE 6	
, F	DWG. NO. S.	1	DWG. BY: FAYPWC	WATER RESOURCES	PAC	2	01/18	ADDED NOTES 5, 8
	DATE: JAN. 01, 20	18	APPROVED BY: J.E.G.	ENGINEERING DEPARTMENT		3		REVISED NOTES 1, 2-a, 2-b, 7 AND 8 FOR NCDOT U-4405.
								S1-SEWER-NOTES.dwg

PRECAST REINFORCED CONCRETE MANHOLES SHALL BE IN ACCORDANCE WITH ASTM C-478.

MINIMUM CONCRETE COMPRESSIVE STRENGTH SHALL BE 4.000PSI.

3. MANHOLES GREATER THAN 12' DEPTH SHALL HAVE MINIMUM 6"

4. FLEXIBLE BUTYL RESIN JOINT SEALANT SHALL BE IN ACCORDANCE VITH ASTM C990. RUBBER GASKET JOINTS SHALL BE IN ACCORDANCE WITH ASTM C-443

5. FLEXIBLE EPDM RUBBER BOOT CONNECTORS SHALL BE IN ACCORDANCE WITH ASTM C923, INSTALLED BY MANUFACTURER WITH STAINLESS STEEL COMPRESSION RING AND TAKE-UP CLAME CONNECTION TO MAIN SHALL BE BY CONTRACTOR WITH STAINLESS STEEL PIPE CLAMP

CONNECTIONS TO EXISTING MANHOLES SHALL BE BY CORING MANHOLE AND FIELD INSTALLING A FLEX BOOT CONNECTOR. DO

MORTAR SHALL BE QUICK SETTING, NON-SHRINK GROUT MIXED IN CCORDANCE WITH MANUFACTURER'S RECOMMENDATION:

8. MANHOLE STEPS SHALL BE IN ACCORDANCE WITH ASTM C478 AND OSHA REGULATIONS. ALIGN STEPS WITH INVERT OU

9. PRECAST INVERTS ARE NOT ALLOWED. STANDING WATER IN

10. VERTICAL DROPS BETWEEN THE INFLOW PIPES AND OUTFLOW PIPES SHALL REQUIRE THE FOLLOWING: A. GREATER THAN 2.5' SEE DROP STRUCTURE DETAIL (MIN. 5' DIAMETER MH REQUIRED B. 1' TO 2.5' SEE PIPE SLIDE DETAIL LESS THAN 1' SEE MORTAR SLIDE DETAIL

11. AN ECCENTRIC CONE SHALL BE UTILIZED ON ALL MANHOLES, UNLESS OTHERWISE APPROVED BY ENGINEER. 12. INVERT ON PLANS IS TO MANHOLE CENTERLINE

STANDARD MANHOLE

DWG. NO. S.2 DWG. BY: FAYPWC

DATE: JAN. 01, 2018 APPROVED BY: J.E.G.

13. CONCRETE GRADE RINGS SHALL NOT BE USED FOR ABOVE GRADE ADJUSTMENTS (IE: OUTFALL AREAS). USE OF GRADE RINGS

FAYETTEVILLE

FAYETTEVILLE, N.C.

WATER RESOURCES

ARE ALLOWABLE IN YARD AREAS AND PAVEMENT. WHERE THE RING

14. THE MINIMUM SLOPE ACROSS THE INVERT OF THE MANHOLE SHALL BE 1%, UNLESS OTHERWISE APPROVED BY ENGINEER.

15. THE EXTERIOR MANHOLE RISER JOINTS, INCLUDING THE JOINT AT THE CONE, SHALL BE SEALED ON THE OUTSIDE BY AN APPROVED JOINT WRAP. THE WRAP SHALL BE IN ACCORDANCE WITH THE UTILITY SPECIAL PROVISIONS.

16. MANHOLE BOOT FOR 4-INCH LATERALS. SHOULD IT BE NECESSARY TO INSTALL A 4-INCH LATERAL INTO A MANHOLE, THE RUBBER BOOT THAT THE LATERAL IS INSERTED INTO SHALL BE SECURELY FASTENED TO THE CORE HOLE BY UTILIZING A STAINLESS STEEL BAND THAT IS TIGHTENED USING A JACK OR A TORQUE WRENCH (DIRECT DRIVE). BOTH STANDARD SIZE AND STEP DOWN BOOTS ARE ALLOWED. THÉ TORQUE WRENCH SHALL BE SUPPLIED BY THE MANUFACTURER. NO OTHER TYPE BANDS OR METHOD OF SECURING THE BOOT TO THE MANHOLE SHALL BE ACCEPTED.

FOR FOUR (4) INCH SDR 26 LATERALS, THE PIPE OUTSIDE DIAMETER RANGE OF THE BOOT SHALL BE 3.5 INCHES TO 4.25

FOR FOUR (4) INCH DUCTILE IRON LATERALS, THE PIPE OUTSIDE DIAMETER RANGE OF THE BOOT SHALL EITHER BE AS FOR VC OR 4.25 INCHES TO 4.81 INCHES


IN ALL CASES, THE BOOT SHALL BE TIGHTENED ON THE LATERAL BY MEANS OF A SINGLE STAINLESS STEEL STRAP THE LATERAL INVERT SHALL BE AT THE TOP OF THE SHELF.


17. NO MORE THAN 4, FOUR INCH LATERALS OR 3, SIX INCH SHALL ENTER A 4' DIAMETER TERMINAL MANHOLE. NO MORE THAN 2 LATERALS (REGARDLESS OF SIZE) SHALL ENTER ALL OTHER 4' DIAMETER MANHOLES. ALL LATERALS SHALL HAVE AN INDIVIDUAL TROUGH. 5' DIAMETER MANHOLES SHALL BE USED IF THE ABOVE CONDITIONS ARE NOT MET.

18. NO MORE THAN 5 LATERALS SHALL ENTER A 5' DIAMETER

19. USE OF TEE-WYES ON LATERALS IS NOT ALLOWED.

20. ALL MANHOLES SHALL BE VACUUM TESTED IN ACCORDANCE





SHELF CONSTRUCTION.

SEAL ANNULUS OVER

AND AROUND PIPE

SOLID BRICK AND

BASE ONLY

NO. 57 STONE

AT DOGHOUSE WITH

FXISTING SANITARY

-6" MIN. COMPACTED 4"x8"x16" SOLID CONCRETE

BLOCKS 180° APART.

DIRECTED BY ENGINEER.

FAYETTEVILLE

PUBLIC WORKS COMMISSION

FAYETTEVILLE, N.C.

WATER RESOURCES

ENGINEERING DEPARTMENT

ASTM A-185 0.12 SQ./IN.

ASTM A-185 0.15 SQ./IN.

ASTM A-185 0.15 SQ /IN.

MANUFACTURER

INSTALLED POLY

PROPYLENE COATED

STEP OVER INVERT

OUT SEE STEP DETAIL

MANHOLE DIAMETER SIZES MAY BE ADJUSTED ON THE PLANS TO REFLECT SPECIAL CIRCUMSTANCES.

FLEXIBLE BUTYL RESIN

SMOOTH FINISH

SEALANT OR RUBBER GASKET

- SEAL INSIDE AND OUTSIDE OF

JOINT WITH FAST SET MORTAR

LIFT HOLES THAT EXTEND THRU THE WALL

REDUCING SLABS ARE NOT ACCEPTABLE ON MANHOLES LESS THAN OR EQUAL TO 6' DIAMETER.

PIPE SIZES | MANHOLE SIZE | MIN. WALL THICKNESS | MIN. REINF. STEEL

21" AND LESS 48" DIAMETER

24" - 36" 60" DIAMETER

72" DIAMETER

COVER SEE DETAIL

(1) 2" GRADE RINGS □

JOINT-

SEALER

FASTENED WITH T304

PIPE CLAMP

STAINLESS STEEL KORBAND

T-300 STAINLESS STEEL

NEW SANITARY SEWER -

MANHOLE BASE SECTION SHALL

BE SUPPORTED ON 4"x8"x16"

STACKED 2 HIGH 180° APART.

SOLID CONCRETE BLOCKS

MANHOLE BASE BY ENGINEER

SANITARY SEWER

DOGHOUSE MANHOLE

(MAINS 15" OR LESS)

DWG. NO. S.3 DWG. BY: FAYPWC


DATE: JAN. 01, 2018 APPROVED BY: J.E.G.

CONTRACTOR SHALL SAWCUT AND

REMOVE EXISTING PIPE CROWN TO

DEBRIS SHALL BE ALLOWED TO ENTER

SEE NOTE 13.



RING AND COVER, SEE DETAIL

- CONC. GRADE RING MAX. (3)

4", (2) 6" OR (1) 2". SEE NOTE

→ ECCENTRIC REDUCER

- JOINT SEALER

(2 TYPES OF RING AND COVER


- SEAL ANNULUS OVER AND SUB GRADE WITH SOLID BRICK AND SECTION B-B NO. DATE REVISION 07/16 ADDED SHEET 2 11/25/08 MADE CHANGES TO NOTES REVISED NOTES AND CALLOUTS FOR 3 07/24/18 NCDOT U-4405. S3-DOGHOUSE-MH.dwg


PROJECT REFERENCE NO. SHEET NO. U-4405 UC-030 DESIGNED BY: AMH DRAWN BY: AMH/AB CHECKED BY: AMH APPROVED BY: MWF 025490 REVISED: NORTH CAROLINA DEPARTMENT OF TRANSPORTATION TILITIES ENGINEERING SEC PHONE:(919)707-6690 FAX: (919)250-4151


UTILITY CONSTRUCTION


NOTE:

ANY REFERENCE TO FAYPWC PROJECT COORDINATOR. PWC COORDINATOR OR FAYPWC (FAYETTEVILLE PUBLIC WORKS COMMISSION) SHALL BE INTERPRETTED AS A REFERENCE TO THE ENGINEER.











S6-RING-COVER.dwg





S13-SEWER-BEDDING.dwg

1. DETAIL TO BE USED IN PAVED AREAS ONLY, ALL OTHER

UNLESS OTHERWISE APPROVED.

FRAME A48-83,CL 30

MANHOLES SHALL BE IN ACCORDANCE WITH DETAIL S.6,


2. MANHOLE FRAME AND COVER SHALL BE MADE OF GRAY


ALL CASTINGS SHALL CONFORM TO THE SHAPE AND

CAST IRON CONFORMING TO ASTM SPEC. A48-83 CL 30/35 RESPECTIVELY, MANUFACTURED BY SAME MANUFACTURER.

DIMENSIONS SHOWN THEY SHALL BE CLEAN AND PERFECT.

23-1/2"





SANITARY SEWER REPAIR SHALL BE APPROVED BY ENGINEER PRIOR TO MAKING

THE REPAIR. IF THE REPAIR IS WITHIN 20' OF AN EXISTING MANHOLE, THE CONTRACTOR

SHALL BE REQUIRED TO REMOVE AND RELAY PIPE TO NEAREST MANHOLE. UNLESS

2. ALL MATERIALS OF CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE UTILITY

3. CONTRACTOR SHALL PROVIDE ALL NECESSARY PUMPS. HEADER PIPE, PUMPING EQUIPMENT, ETC. PRIOR TO BEGINNING CONSTRUCTION. DUPLICATE SEWAGE HANDLING PUMPS, PIPING, ETC. SHALL BE ON-SITE AND AVAILABLE FOR IMMEDIATE USE SHOULD PRIMARY PUMP OR FORCE MAIN FAIL. INSURE PUMPS, HEADER PIPING, ETC. ARE

BE THE SAME AS THE EXISTING PIPE SLOPE. DEFLECTIONS OF HORIZONTAL AND

6. REPLACEMENT PIPE SHALL BE PROPERLY BEDDED IN ACCORDANCE WITH

I. PIPE REPAIR SHALL EXHIBIT STRAIGHT HORIZONTAL ALIGNMENT AND INVERT SHALL

PIPE SHALL BE BACKFILLED AND COMPACTED IN ACCORDANCE WITH THE UTILITY

7. THERE SHALL BE NO MORE THAN 1/4" SPACE BETWEEN THE EXISTING SEWER MAIN

8. DAMAGED SECTION SHALL BE CUT OUT WITHOUT DAMAGING THE PIPE TO REMAIN.

9. DI SEWER PIPE AND FITTINGS SHALL HAVE AN INTERIOR COATING OF CERAMIC

10. DI PIPE SHALL BE UTILIZED WHEN STATE MINIMUM SEPARATION REQUIREMENTS

11. PIPE REPAIRS ON MATERIALS OTHER THAN SHOWN, SHALL BE AS DIRECTED BY

FAYETTEVILLE

FAYETTEVILLE, N.C.

PUBLIC WORKS COMMISSION

WATER RESOURCES

ENGINEERING DEPARTMENT

12. THE MINIMUM LENGTH OF REPAIR SHALL BE 5 FEET, UNLESS OTHERWISE DIRECTED


SPECIAL PROVISIONS.

STANDARD DETAIL S.13.


VERTICAL ALIGNMENT ARE NOT ACCEPTABLE.

AND THE REPLACEMENT PIPE AT EACH END.

CANNOT BE MET OR AS DIRECTED BY ENGINEER.




S11-RESSLAT-NOTES.dwg





UTILITY CONSTRUCTION


NOTE:

ANY REFERENCE TO FAYPWC PROJECT COORDINATOR, PWC COORDINATOR OR FAYPWC (FAYETTEVILLE PUBLIC WORKS COMMISSION) SHALL BE INTERPRETTED AS A REFERENCE TO THE ENGINEER.









ECCENTRIC MANHOLE CONES MAY BE USED ON 8" AND 10" SEWER MAINS. FLA TOP MANHOLES MAY BE REQUIRED. CONTRACTOR TO REFERENCE PLANS

MIN 8" WIDE BUTYL

RUBBER SEAL ON ALL BELOW-GRADE JOINTS

CONCRETE COLLAR

POSSIBLE - SEE NOTE 6

FOR EXISTING

REVISION

REVISED PER NCDOT COMMENTS (U-4405)

ALL AROUND, SEE

ALL WORK AND MATERIALS TO BE IN

MANHOLE WITH A TYPICAL CHIMNEY

CONTRACTOR TO MEASURE THE INSIDE

SELECT APPROPRIATE DIAMETER OF NEW

CONTRACTOR TO REMOVE EXISTING WALLS

TO SOLID STRUCTURE (TO AT LEAST BELOW

THEIR SPECIFIED LOCATION. THE LIMITS OF

THE CONE OR CHIMNEY SECTION) OR TO

REMOVAL SHALL BE APPROVED BY THE

ALSO REMOVE EXISTING FRAMES AND

DISPOSE OF ALL MATERIALS OFF-SITE.

COVER, VENT PIPES AND ALL

THE MANHOLE TO THE

ENGINEER IN THE FIELD, CONTRACTOR TO

APPURTENANCES, ETC. CONTRACTOR TO

CONE SECTIONS AS NECESSARY TO EXTEND

SPECIFIED/APPROVED ELEVATION. THE

FINAL ELEVATION MAY BE HIGHER THAN

ELEVATION. THIS DETAIL ILLUSTRATES A

SHALL DETERMINE THE REQUIRED RISER

APPROVE FINAL ELEVATIONS IN THE FIELD.

BOTTOM RISER TO BE PROVIDED WITH A

HIGHER ELEVATION THE CONTRACTOR

AND CONE HEIGHTS TO MEET THE

FLAT JOINT UNLESS OTHERWISE

CONTRACTOR TO INSTALL NEW RISER

PROVIDE A LEAK-TIGHT JOINT. THE CONTRACTOR SHALL PERFORM ALL WORK

SECTION/EXISTING WALL JOINT TO BE

NECESSARY TO PROVIDE A LEAK-TIGHT

SEAL, WHERE POSSIBLE, BUTYL RUBBER

NEW RISER SECTION. IN ALL CASES, A

CONCRETE COLLAR SHALL BE POURED

SEAL JOINT WITH NON-SHRINK GROUT.

GROUT TO COMPLETELY FILL JOINT AND

SHALL EXTEND AT LEAST 6 INCHES EACH

SIDE OF JOINT ALL AROUND. GROUT TO BE

BELOW THE JOINT. GROUT TO BE

1 OF 1 DATE: 5/18/2015

RESISTANT TO HYDROGEN-SULFIDE.

AROUND THE JOINT. COLLAR TO BE MINIMUM 6 INCHES WIDE AND 12 INCHES

SEALANT SHALL BE PROVIDED UNDER THE

HIGH CENTERED ON JOINT ALL AROUND. ON

THE INSIDE OF THE JOINT, CONTRACTOR TO

APPROVED.

LOWER THAN OR EQUAL TO THE EXISTING

CONTRACTOR TO INSTALL NEW RISER AND REMOVE PORTION

SPECIFIED ELEVATION. ENGINEER SHALL EXISTING MANHOL

DIAMETER OF EXISTING MANHOLE TO

THIS DETAIL DEPICTS AN EXISTING BRICK

SOLID OR WATERTIGHT

MANHOLE, SEE NOTES 3&4

FILL INSIDE JOINT

GROUT, SEE NOTE

DIRECTED ON PLANS

REQUIRED

DIAMETER VARIES

RAISE AND REPLACE EXISTING MANHOLE

NO. DATE

PATH AND FILENAME:

1 7/24/2018

ACCORDANCE WITH THE UTILITY


SPECIAL PROVISIONS.

PROJECT REFERENCE NO. SHEET NO. U−4405 UC-03Q DESIGNED BY: AMH DRAWN BY: AMH/AB CHECKED BY: AMH APPROVED BY: MWF 025490 REVISED: NORTH CAROLINA DEPARTMENT OF TRANSPORTATION Mark W. Justy JTILITIES ENGINEERING SEC PHONE:(919)707-6690 FAX:(919)250-4151

UTILITY CONSTRUCTION

NOTE:

ANY REFERENCE TO FAYPWC PROJECT COORDINATOR, PWC COORDINATOR OR FAYPWC (FAYETTEVILLE PUBLIC WORKS COMMISSION) SHALL BE INTERPRETTED AS A REFERENCE TO THE ENGINEER.



NOTE:

COFFER DAM AND STREAM BYPASS PUMP AROUND SHALL BE INCIDENTAL TO THE SEWER LINE CONSTUCTON. NO SEPARATE PAYMENT SHALL BE MADE FOR ITS INSTALLATION, UPKEEP AND REMOVAL.

